

SECTION 01 51 36
TEMPORARY WATER

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Requirements for Temporary Water

1.02 RELATED REQUIREMENTS

- A. Section 01 31 00 - Project Management and Coordination
- B. Section 01 52 19 - Temporary Sanitary Facilities

1.03 GENERAL REQUIREMENTS

- A. Installation and Maintenance: If required for the execution of the Work, the Contractor shall provide, install, and maintain a temporary water system, including the necessary temporary water lines, valves, fittings, pumps, and other appurtenances, all of such size and capacity as to adequately supply the needs of the Contract. Any repairs required due to such use shall be made at the expense of the Contractor. If required, one 100-foot long hose and one water nozzle shall be supplied by the Contractor, for use in outside work areas throughout the job site.
- B. Responsibility for Damage: The Contractor shall be responsible for any damages caused for reason of leaky, defective or broken piping connections or other appurtenances installed under this Section.
- C. When temporary water is provided: If necessary, temporary water shall be provided by the Contractor from 8AM to 4PM every regular working day for all trades. Should it be necessary, subject to the approval of NYCHA, for the Contractor to perform work before or after the hours set forth above or on a day other than a regular working day, the Contractor shall secure NYCHA's approval and make arrangements for such additional temporary water and toilet facilities.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION