



AT NON - PARKING AREAS
NOTES:

1. VERTICAL AND HORIZONTAL REBARS SHALL BE FIELD TIED. WELDING IS NOT PERMITTED. THE CONTRACTOR SHALL SUPPORT REINFORCEMENT IN ITS PROPER LOCATION FROM THE FRAMEWORK DURING CONCRETE OPERATION.
2. THE CONTRACTOR SHALL REMOVE WATER PRESENT IN HOLE PRIOR TO POURING CONCRETE.
3. THE CONTRACTOR SHALL VERIFY ALL INFORMATION PERTAINING TO THE POLE AND FIXTURE INSTALLATION WITH THE MANUFACTURER. THE ENGINEER AND/OR OWNER TO BE NOTIFIED OF ANY DISCREPENCIES.
4. INSTALLATION OF POLE FOOTING IN CONCRETE PAVING REQUIRES 1/2" EXPANSION JOINT FILLER SEALED WITH JOINT SEALANT.
5. POLE BASE DIMENSIONS, REBAR QUALITY AND SIZES TO BE AS REQUIRED TO SUIT SITE CONDITIONS, DESIGN REQUIREMENTS, SPECIFICATIONS, AND ALL CODE REQUIREMENTS.
6. ALL CONDUIT MUST BE BURIED AT LEAST 3' BELOW GRADE.
7. THE INFORMATION ILLUSTRATED IN THE LIGHT POLE FOUNDATION DETAIL HAS BEEN PROVIDED FOR GENERAL REFERENCE AND PRELIMINARY COST ESTIMATE PURPOSES. LIGHT POLE FOUNDATIONS SHOULD BE DESIGNED AND DETAILED BY A LICENSED STRUCTURAL ENGINEER BASED ON EXISTING SOIL CONDITIONS, LOCAL DESIGN STANDARDS AND MANUFACTURERS RECOMMENDATIONS.
8. SEE DETAIL FOR REBAR SCHEDULE

WAL-11



New York City Housing Authority
Capital Projects Division
Design Department
90 Church Street, 10th Floor
New York, NY 10007

Title:

**LIGHT POLE FOUNDATION,
POLE BASE & GROUNDING
AT PLANTED AREAS**

Contract Name:

GROUNDS REQUIREMENT

Contract No.

GD XXXXXXX

Drawn by:

G. SOUKAS

Checked by:

K. MARSHAL

Scale:

Not to Scale

Date:

January 2017

Drawing No.

ELE- 01