

NOTES:


PRECAST UNIT PAVERS SHALL HAVE A COMPRESSIVE STRENGTH OF GREATER THAN 8000 psi, AND SHALL MEET THE REQUIREMENTS SET FORTH IN ASTM C936. PIGMENT IN CONCRETE PAVERS SHALL CONFORM TO ASTM C979.

THE UNIT PAVERS SHALL BE CAREFULLY LAID TO ENSURE JOINTS ARE NO MORE THAN 1/8". WHERE REQUIRED, PAVING STONES SHALL BE CUT WITH AN APPROVED CUTTER TO FIT NEATLY AND ACCURATELY, WITHOUT DAMAGING EDGES. SAND SHALL BE SWEEP INTO JOINTS.


THE DEPTH OF THE UNIT PAVERS SHALL BE 2 3/8".

STONE SCREENINGS SHALL NOT EXCEED 1/4" DIAMETER.
MANUFACTURER, PATTERN AND COLOR TO BE DETERMINED


SEE DETAIL FOR REBAR SCHEDULE (WAL-11)



HERRINGBONE PATTERN



BASKET WEAVE PATTERN



RUNNING BOND PATTERN



New York City Housing Authority
Capital Projects Division
Design Department
90 Church Street, 10th Floor
New York, NY 10007

Title:

**CONCRETE UNIT PAVERS
On Rigid Base**

Contract Name:

GROUNDS REQUIREMENT

Contract No.

GD XXXXXXX

Drawn by:

G. SOUKAS

Checked by:

K. MARSHAL

Scale:

Not to Scale

Date:

January 2017

Drawing No.

PAV- 15