



**NOTE -**

THE TWO (2) REBARS AT THE TOP OF THE CURB SHALL BE 1/2" CLEAR FROM THE SIDES AND 2" CLEAR FROM THE TOP OF THE CURB.  
 THE TWO (2) REBARS AT THE BOTTOM OF THE CURB SHALL BE 1/2" CLEAR FROM THE SIDES AND 3" CLEAR FROM THE BOTTOM OF THE CURB.  
 FENCE POST SHALL BE LOCATED A MINIMUM OF 18" FROM EXPANSION JOINT(S).

SEE DETAIL FOR REBAR SCHEDULE

(WAL-11)



New York City Housing Authority  
 Capital Projects Division  
 Design Department  
 90 Church Street, 10th Floor  
 New York, NY 10007

Title:

**FLUSH CONCRETE CURB  
 for Steel Bar Fence**

Contract Name:

**GROUNDS REQUIREMENT**

Contract No.

GD XXXXXX

Drawn by:  
G. SOUKAS

Checked by:  
K. MARSHAL

Scale:

Not to Scale

Date:

January 2017

Drawing No.

**CUR- 07**