



TREE SHALL BE LIMBED UP TO 6'-0". EXCEPT IN PEDESTRIAN AND VEHICULAR AREAS WHERE TREE SHALL BE LIMBED UP TO 7'-0"

NOTES-

FOR ROOT BALL - WHEN SYNTHETIC BURLAP IS USED REMOVE COMPLETELY BEFORE PLANTING TREE. WHEN WIRE CAGE IS USED TOP 1/3 OF CAGE SHALL BE CUT AND REMOVED.

DURING BACKFILLING, MACROTABS AND MYCORRHIZAL INNOCULANT BY PLANT HEALTH CARE INC., 440 WILLIAM PITT WAY PITTSBURGH, PA 15238 412 826-5445, OR APPROVED EQUAL SHALL BE MIXED INTO THE TOP 8" OF TOPSOIL MIXTURE, FOLLOWING MANUFACTURER'S INSTRUCTIONS. SEE SPECS.

1" CHAIN LOCK TREE TIE BY AMERICAN ARBORIST SUPPLIES, INC 1.800.441.8381 OR APPROVED EQUAL.

CEDAR STAKE, 8'-0" LONG, 3" DIA. -SEE SPEC FOR # REQUIRED.

TREE WRAPPING 50% OVERLAP DURING INSTALLATION AND CONSTRUCTION, REMOVE AFTER COMPLETION OF FINAL PUNCHLIST WORK

3" MULCH, 3" CLEAR FROM TRUNK

3" SAUCER RIM

FINISHED GRADE

CUT AND REMOVE BURLAP FROM TOP 1/3 OF ROOT BALL

TOPSOIL MIXTURE SHALL BE BACKFILLED TO THE TOP OF THE ROOT BALL. INSTALL A MIN. OF 1' AROUND ROOT BALL OR ALIGN WITH TREE GRATE WHEN USED. UNLESS OTHERWISE SHOWN ON DRAWINGS.

SUBGRADE

6" COMPACTED TOPSOIL

TREE GRATE or GRANITE BLOCK SEE PLANS & SPECS.
FINISHED GRADE SEE PLANS

3/4" DIA. GRAY PEA GRAVEL

IF ROOT COLLAR IS NOT EXPOSED, REMOVE SOIL FROM TOP OF ROOT BALL UNTIL TRUNK FLARE IS LOCATED. FINISHED GRADE SHALL BE SET AT THE BOTTOM OF THE FLARE AS SHOWN

PAVED AREA | PLANTED AREA
- SEE PLANS -

3X ROOT BALL WIDTH



New York City Housing Authority
Capital Projects Division
Design Department
90 Church Street, 10th Floor
New York, NY 10007

Title:

TREE PLANTING-Paved or Planted Area

Contract Name:

GROUNDS REQUIREMENT

Contract No.

GD XXXXXXX

Drawn by:
G. SOUKAS

Checked by:
K. MARSHAL

Scale:

Not to Scale

Date:

January 2017

Drawing No.

PLT- 04