



AFTER ANCHORING COMPOUND HAS HARDENED, CROWNING GROUT SHALL BE TROWELED IN TO FILL AND SEAL THE HOLES AND FORM A ¼ INCH WASH. CROWNING GROUT SHALL BE "HBA REPAIR MORTAR" AS MANUFACTURED BY BASF CONSTRUCTION CHEMICALS, LLC, OR APPROVED EQUAL. SEE SPECS.

ANCHORING COMPOUND FOR POSTS SHALL BE "EMACO GRIP", AS MANUFACTURED BY BASF CONSTRUCTION CHEMICALS, LLC, OR APPROVED EQUAL. FILL TO WITHIN 1 INCH OF THE TOP OF POST HOLE. SEE SPECS.

EXISTING OR NEW CONCRETE CURB/ WALL /FOOTING/ PAVEMENT - SEE PLANS.

**NOTES-**

POST SHALL BE SET TO THE SPECIFIED DEPTHS IN THE CORED HOLES OF THE CONCRETE CURB, WALL, OR EXISTING STRUCTURE AS SHOWN. POSTS SHALL BE SET PLUMB, PROPERLY ALIGNED AND ANCHORED FIRMLY IN PLACE. HOLES IN FOOTINGS SHALL BE FORMED.

FOR STEEL BAR FENCE, THE DIAMETER OF THE HOLE SHALL BE AS SHOWN ON THE FENCE DETAIL. FOR ROUND POSTS, THE DIAMETER OF THE HOLE SHALL NOT EXCEED THE OUTSIDE DIAMETER OF THE POST IT IS TO RECEIVE BY MORE THAN 1", UNLESS OTHERWISE NOTED.

 <p>New York City Housing Authority Capital Projects Division Design Department 90 Church Street, 10th Floor New York, NY 10007</p>	Title:		<i>POST GROUTING</i>	
	Contract Name:	Contract No.	Scale:	Drawing No.
GROUNDS REQUIREMENT	GD XXXXXXX	Not to Scale	<b>MIS- 01</b>	
	Drawn by: G. SOUKAS	Checked by: K. MARSHAL		Date: January 2017